



GOVERNMENT OF NATIONAL CAPITAL TERRITORY OF DELHI
HEADQUARTERS: DELHI FIRE SERVICE: NEW DELHI-110001



No. F6/DFS/MS/2025/School/ 293

Dated: 27/03/2025

FIRE SAFETY CERTIFICATE

Certified that the Shree Ram International School located at Khasra No- 16/3, Gali No-9, Block-D, Nathu, Colony, Nathupura, Delhi-110084 comprised of Ground & 03 upper floors only owned/ occupied by the Shree Ram International School have complied with the fire prevention and safety requirements in accordance with rule 33 of Delhi Fire Service Rules, 2010 and verified by the officer concerned of Fire Service on 19.03.2025 in the presence of Sh. Manoj Kumar (Manager) and that the building/premises is fit for occupancy Class "Group B Educational (School)" with effect from 27/03/2025 for a period of three years, in accordance with the rule 36 unless renewed under rule 37 or sooner cancelled under rule 40 and subject to compliance of the conditions under rule 38 of the Delhi Fire Service Rules, 2010.

Issued on ... 27/03/2025 ... at New Delhi


 (Atul Garg)
 Director

Ph:-011-23414000



Copy to: -

1. The Deputy Director of Education, GNCT of Delhi, Zone-VII, District North Lucknow Road, Timarpur, Delhi - 110054.
2. The Manager, Shree Ram International School located at Khasra No- 16/3, Gali No-9, Block-D, Nathu, Colony, Nathupura, Delhi-110084.

Conditions for the validity of Fire Safety Certificate:

- 1 All the means of escape/entry/exit shall be kept free from any obstruction.
- 2 All the fire safety arrangements provided therein shall be maintained in good working condition at all time as seen during inspection. Any loss of life or property due to non-functional fire safety measures shall be at the responsibility of the management.
- 3 All the staff members must know the correct method of operation of firefighting system.
- 4 The owner / occupier shall submit a declaration every year in Form "K" provided in the first schedule of Delhi Fire Service Rules 2010. The form is available on <http://delhi.gov.in/wps/wcm/connect/doit/fire/FIRE/Home/Forms>.
- 5 This fire safety certificate may not in any way be treated as regularization (Clause 2.8 of UBBL-2016) of unauthorized construction or Alteration (Clause 1.4.3 of UBBL-2016), if any.
- 6 "The owner/occupier shall apply for renewal of this Fire Safety Certificate to the Director in Form 'J' [sub rule (1) of rule 37] along with a copy of this Certificate, six months prior to its expiry".

INSPECTION REPORT

1. Name & address of the building : Shree Ram International School at Kh. No- 16/3, Gali No-9, Block-D, Nathu Colony, Nathupura, Delhi-110084.
2. Type of Occupancy : Educational
3. Type of Case : New Case
4. Composition of building : Ground & 03 upper floor
5. Details of previous NOC : Nil
6. Fire Safety directives letter No : NBC Part-4
7. Date of inspection : 19.03.2025
8. Name of the Inspecting Officers : ADO (RN)
9. Name and designation of officers from the building side : Sh. Manoj Kumar (Manager)
10. Year of Construction : 2017
11. Applicant's letter No. : Letter No-nil dated 20.02.2025


	Minimum Standards on fire prevention and fire safety U/R 33	NBC Part-IV/ UBBL Requirements	Provided at site	Remarks MR/NMR
1	Access to building			
	• Road width	06m	06m	MR
	• Gate width	Directly accessible	Directly accessible	MR
	• Width of internal road	NA	NA	NA
2	Number, Width, Type & Arrangement of Exits			
	a. Number of staircases			
	• Upper Floors	02	02	MR
	• Basements	NA	NA	NA
	b. Width of staircases			
	• Upper Floors	1.50m <i>each</i>	1.50m <i>each</i>	MR
	• Basements	NA	NA	NA
	c. Protection of exits			
	• Fire check door	NA	NA	NA
	• Pressurization	NA	NA	NA
	d. No. of continuous staircases to terrace	02	02	MR
	e. Width of Corridor	1.50m	2.40m	MR
	f. Door Size	1.20m	1.20m	MR
3	Compartmentation.			
	• Fire check door	NA	NA	NA
	• Sealing of electrical shafts	NA	NA	NA
	• Fire Rating of shaft door	NA	NA	NA
	• Water Curtain	NA	NA	NA
	• Fire Dampers	NA	NA	NA
4	Smoke Management System.			
	• Basements	NA	NA	NA
	• Upper floors	Required	Natural Ventilated	MR
5	Fire Extinguishers.			
	• Total numbers	10nos	Provided	MR
	• Types	ABC/Co2	Provided	MR
	• ISI marking	ISI Marked	Provided	MR
6	First-Aid Hose Reels.			

	<ul style="list-style-type: none"> Total numbers on each floor Length of hose reel hose Nozzle diameter 	01	Provided	MR
		30m	30m	MR
		5mm	5mm	MR
7	Automatic fire detection and alarming system.			
	<ul style="list-style-type: none"> Type of detectors Location of Main Panel Location of Repeater Panel Alternate source of power Hooters' Location 	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
		NA	NA	NA
8	MOEFA	NA	NA	NA
9	Public Address System.	NA	NA	NA
10	Automatic Sprinkler System.			
	<ul style="list-style-type: none"> Basement Upper Floor Sprinkler above false ceiling 	NA	NA	NA
		NA	NA	NA
		NA	NA	NA
11	Internal Hydrants			
	<ul style="list-style-type: none"> Size of riser/down-comer Number of hydrants per floor Hose Box 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
12	Yard Hydrants.			
	<ul style="list-style-type: none"> Total number of hydrants Hose Box 	NA	NA	NA
		NA	NA	NA
13	Pumping Arrangements.			
	<ul style="list-style-type: none"> Ground Level <ul style="list-style-type: none"> Discharge of main Pump Head of Main pump Number of main pumps Jockey Pump out put Jockey pump head Standby Pump out put Standby Pump Head Auto Starting/ Manual stopping Pump House Access Terrace level <ul style="list-style-type: none"> Discharge of pump Head of the pump Power Supply Auto Starting of pump 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		450 LPM	Provided	MR
		40m	40m	MR
		Required	Provided	MR
		Required	Provided	MR
14	Captive Water Storage for fire fighting.			
	<ul style="list-style-type: none"> Underground tank capacity <ul style="list-style-type: none"> Draw-off connection Fire service inlet Access to tank Overhead Tank capacity 	N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		N/A	N/A	N/A
		10,000 LTR	Provided	MR
15	Exit Signage	Required	Provided	MR



16	Provision of Lifts.			
	• Pressurization of Lift Shaft	N/A	N/A	N/A
	• Pressurization of Lift lobby	N/A	N/A	N/A
	• Communication In lift Car	N/A	N/A	N/A
	• Fireman's Grounding Switch	N/A	N/A	N/A
	• Lift Signage	N/A	N/A	N/A
17	Standby power supply	Required	Provided	MR
18	Refuge Area.			
	➤ Total Area	N/A	N/A	N/A
	➤ Location	N/A	N/A	N/A
19	Fire Control Room			
	• Detector System Panel	N/A	N/A	N/A
	• Flow Switch Panel	N/A	N/A	N/A
	• PA System Panel	N/A	N/A	N/A
	• Batter backup	N/A	N/A	N/A
	• Building Floor Plans	N/A	N/A	N/A
20	Special Fire Protection Systems for Protection of special Risks, if any:	N/A	N/A	N/A

The fire protection systems provided in the building were tested/ checked randomly and found in good working condition at the time of inspection. The management has complied all the shortcomings issued and communicated by this department vide letter of even no. F6/DFS/MS/2024/School/616 dated 10.09.2024.

Keeping in view the satisfactory compliance of the minimum standards on fire prevention and fire safety required as stipulated in NBC Part-IV, it is recommended to grant Fire Safety Certificate.


 Signature of the Inspecting Officer
 Name:-C.L. Meena
 Designation:- Asst. Div. Officer (RN)

DO (NW)


 21/03/2025

 Director
 21/03/2025

DCFOI
 1025 N/10
 21/3/2025